

Addendum/ Corrigendum in RFP - Road Repair & Maintenance Work

Sr. No.	As Mentioned in RFP	Amended
1	3.1 of NIT Pg No. 12, Point no. 1.1 (a) (i) Bituminous Work using SDBC/BC Material manufactured with Bitumen of grade VG-30 . In Bituminous Batch mix plant of 100-120TPH capacity and Sensor paver of 7 m width for excessive damaged/cracked carriageway.	3.1 of NIT Pg No. 12, Point no. 1.1 (a) (i) Bituminous Work using SDBC/BC Material manufactured with Bitumen of grade VG-40 . In Bituminous Batch mix plant of 100-120TPH capacity and Sensor paver of 7 m width for excessive damaged/cracked carriageway.
2	Clause 31 Advance Payment of 3.1 NIT , Pg No. 27 The Employer will provide an interest free mobilization Advance Payment on the Contract Price to the Contractor, as per Clause 44 of GCC (Section 3.3) subject to a maximum amount as stated in Contract Data.	Clause 31 Advance Payment of 3.1 NIT , Pg No. 27 The Employer will provide mobilization Advance Payment on the Contract Price to the Contractor, as per Clause 44 of GCC (Section 3.3) subject to a maximum amount as stated in Contract Data. Interest @ 8% will be charged after 2 months of advance payment.
3	Annexure 1A, Pg. No. 29 *Batch Type Hot Mix plant (100-120 ton per Hr) with all electronic controls *Sensor Paver finisher (7Mtr Width) (not older than year 2018) *Micro Surfacing machine with hydraulic power not older than 3 years.	Now Annexure 1A, Pg. No. 29 to be read as: *Batch Type Hot Mix plant (100-120 ton per Hr) with all electronic controls well in working condition *Sensor Paver finisher (7Mtr Width) well in working condition *Micro Surfacing machine with hydraulic power well in working condition
4	Liquidated Damages and Penalty N/A, Pg no. 70	For delay in work Penalty @ Rs. 5000 per day beyond justified date of completion
5	Payment certificate, Pg no. 69, Point no. 39.1 (f) (i) Contractor to submit a payment request with details of Works completed or partly completed during the calendar month to the Engineer, within seven days from the last date of the particular month;	Contractor to submit a payment request with details of Works completed or partly completed during the calendar month to the Engineer, within seven days from the last date of the particular month. Computerised bill on A4 Size sheet supported by minimum 6 Photograph "5"*"7" & 6 videos not less than 5 minutes each of ongoing work
6	Payment certificate, Pg no. 69, Point no. 39.1 (f) (ii) Within Seven days of receipt of Contractor's RA Bill, Engineer is required to evaluate the payment request in terms of the work executed, and if the Engineer finds the payment request in order, he certifies to pay 70% of eligible payment against the RA Bill, which shall be released by Authority in next 7 days. This payment shall be net of recovery of mobilization and other advances, recovery in terms of Contract and Taxes to be deducted at source as applicable under the Law	(ii) 70% is replaced by 90%
7	Form- 6B -Letter of Acceptance, Point No. 5, Pg. no. 96 3.The date of start will be as defined in S. No. 5 of Contract Data. 5.You are requested to please furnish the Performance Security in the form of Bank Guarantee for an amount equal to 5% of the Contract price within 14 days of receipt of this letter, in accordance with Clause 33 of ITB and Clause 45 of GCC as defined in the Contract Data S. No. 19 . The Bank Guarantee will be provided in the proforma given in the Bid Document. 6. You are also requested to sign and execute the Contract Agreement within 28 days, failing which action as stated in Para 33.2 of ITB will be taken.	Form- 6B -Letter of Acceptance, Point No. 5, Pg. no. 96 3. The date of start will be considered after 10th day of the issuance of the letter of acceptance. 5.You are requested to please furnish the Performance Security in the form of Bank Guarantee for an amount equal to 5% of the Contract price within 7 days of receipt of this letter, in accordance with Clause 30 of ITB and Clause 45 of GCC as defined in the Contract Data S. No. 18 . The Bank Guarantee will be provided in the proforma given in the Bid Document. 6. You are also requested to sign and execute the Contract Agreement within 28 days, failing which action as stated in Para 30.2 of ITB will be taken.
8	Form -6E (Please refer Clause 25.3 of ITB) , Pg No. 101,	Form -6E (Please refer Clause 29.3 of ITB) , Pg No. 101
9	BOQ, item 9.1, Pg. no. 106 25 mm compacted thickness with bitumen of grade VG- 30@5% (percentage by weight of total mix) and lime filler @ 2% (percentage by weight of Aggregate) prepared in Batch Type Hot Mix -120 TPH capacity	BOQ, item 9.1 25 mm compacted thickness with bitumen of grade VG- 40@5% (percentage by weight of total mix) and lime filler @ 2% (percentage by weight of Aggregate) prepared in Batch Type Hot Mix 100-120 TPH capacity

10	BOQ, item 10.1, Pg. no. 106 40/50 mm compacted thickness with bitumen of grade VG-30 @ 5.5 % (percentage by weight of total mix) and lime filler @ 3% (percentage by weight of Aggregate) prepared in Batch Type Hot Mix Plant of 100- 120 TPH Capacity.	BOQ, item 10.1 40/50 mm compacted thickness with bitumen of grade VG-40 @ 5.5 % (percentage by weight of total mix) and lime filler @ 3% (percentage by weight of Aggregate) prepared in Batch Type Hot Mix Plant of 100- 120 TPH Capacity.
----	--	---