

Name of Work: Cleaning of storm water drains & chambers at DND Flyway during 2024-2025

S.No.	Description of Items	Qty	Unit	Rate	Amount(in Rs.)
1	Clearing road side/Median open lined/ pucca drains/covered drains/ gratings, channels and Galis etc. of all sizes and bring them to original shape, drainage capacity including disposal of sediments, extraneous debris & vegetation growth blocking the free flow from site outside ROW with all leads and lifts complete in all respects as directed by the Engineer in charge (frequency of cleaning will be twice in a year i.e. before and after monsoon.)	7000	RM		
2	Fixing MS jail with Kerb stones to prevent entry of rubbish into SW drain/ chamber including all nuts , bolt and screw required etc. as per direction of Engineer-in charge complete.(MS jail will be issued free of cost.)	150	each		
	Total Amount Rs.				

Condition:

1. Work will be executed as per CPWD and MORTH specification
2. Necessary recoveries like income tax and GST will be recovered
3. 90 days' time will be allowed for execution of work after letter of award.
4. All T&P will be arranging by the contractor/Bidder.